Final Bill of Materials

Scaff Ref # 000003 **Description:**

Material Type	Item Code	Description	Item Weight (kg)	Quantity	Total Weight (kg)
Conventional	Tube0900	0.9m Scaffold Tube	4.05	4	16.2000
Conventional	Tube1500	1.5m Scaffold Tube	6.75	5	33.7500
Conventional	Tube1800	1.8m Scaffold Tube	8.10	6	48.6000
Conventional	Tube2100	2.1m Scaffold Tube	9.45	7	66.1500
KwikStage	KwkStd20	Kwk Standard 2.00m	12.15	5	60.7500
KwikStage	KwkStd25	Kwk Standard 2.50m	14.82	6	88.9200
KwikStage	KwkStd30	Kwk Standard 3.00m	17.49	7	122.4300
Layher	L5606150	Diagonal Brace 1.57m x 1.5m	7.30	9	65.7000
Layher	L5607050	Diagonal Brace 2.57m x 0.5m	8.40	8	67.2000
Layher	L5607100	Diagonal Brace 2.57m x 1.0m	8.80	6	52.8000
Layher	L5607150	Diagonal Brace 2.57m x 1.5m	9.50	5	47.5000
KwikStage	KwkStdTop	Kwk Standard Topper	1.55	8	12.4000
KwikStage	KwkStd05	Kwk Standard 0.50m	5.02	9	45.1800
Conventional	Tube1200	1.2m Scaffold Tube	5.40	1	5.4000
			Total:	86	0.733 Tonnes

Printed: 12-Feb-2018